



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site							
S.No.	Testing Kit	Name of Test	Test Details	Reference IS Code	Testing Subdivision	Unit	Rates in Rs.
1	Domestic Testing Kit	Earth Testing	Measurement of Earth Resistance.	IS 3043: 1987 (RA 2016)	--	Per Earth Pit	900
		Energy Meter Testing	Check meter reading is accurate or not.	IS 15707: 2006 (RA 2016)	Single Phase	Each	600
					Three Phase	Each	850
		LUX (Light Level) Measurement	Check light level for a particular area.	IS 3646 PART-1 1992 (RA 2008)	ROOM	Per Room	250
					For 1-BHK	Each	700
					For 2-BHK	Each	950
					For 3-BHK	Each	1200
		Wire Insulation Resistance & Continuity Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 694 : 2010 (RA 2015)	For 4-BHK	Each	1550
					CIRCUIT	Per Circuit	100
					For 1-BHK	All Circuits	850
					For 2-BHK	All Circuits	1000
		Polarity Test for Switch	Check that apparatus have correct connectivity.	IS 732: 1989 (RA 2015) Clause 12.3.10	For 3-BHK	All Circuits	1400
					For 4-BHK	All Circuits	1700
		Visual Inspection of MCB, ELCB & Distribution Board as per load	Check ratings and connectivity is ok or not.	IS/IEC 60898-1: 2002 Clause 9.10.1	--	Per Switch Board	50
					Single Phase	Per Dist. Board	450
		Over All testing Package			Three Phase	Per Dist. Board	650
For 1-BHK	Each				3300		
For 2-BHK	Each				4000		
For 3-BHK	Each				5000		
			For 4-BHK	Each	5500		

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site									
2	Residential Society Testing Kit	Earth Testing	Measurement of Earth Resistance.	IS 3043: 1987 (RA 2016)	--	Per Pit	700		
		Energy Meter Testing	Check meter reading is accurate or not.	IS 15707: 2006 (RA 2016)	Single Phase	Each	600		
		LUX Measurement	Check light level for a particular area.	IS 3646 PART-1 1992 (RA 2008)	Three Phase	Each	900		
					--	Per Room	250		
					For 1-BHK	Each	700		
					For 2-BHK	Each	950		
		Wire Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 694 : 2010 (RA 2015)	For 3-BHK	Each	1200		
					For 4-BHK	Each	1550		
					--	Per Circuit	100		
					For 1-BHK	All Circuits	850		
		Polarity Test for Switch	Check that apparatus have correct connectivity.	IS 732: 1989 (RA 2015) Clause 12.3.10	For 2-BHK	All Circuits	1000		
					For 3-BHK	All Circuits	1400		
					For 4-BHK	All Circuits	1700		
					--	Per Switch Board	50		
		Visual Inspection of MCB, ELCB & Distribution Board as per load	Check ratings and connectivity is ok or not.	IS/IEC 60898-1: 2002 Clause 9.10.1	Single Phase	Per Dist. Board	450		
					Three Phase	Per Dist. Board	650		
		Transformer Test	1. Oil Level Checking in Conservator 2. No Load Loss & Current 3. Terminations Connections on HV & LV Cable Box 4. Short Circuit Impedance & Load Loss at 50% & 100% Load 5. Oil & Winding Temperature Measurement & Inspection of Buchholz Relay 6. Insulation Resistance & Winding Resistance Test 7. Voltage Ratio Test 8. Magnetic Balance Test 9. Phase Displacement Test 10. Oil Break Down Voltage Test (In Lab)	IS 10028 Part 3: 1981 (RA-2008)	Upto 250 KVA	Each	20000		
					251 TO 500 KVA		24000		
					501 TO 1000 KVA		28750		
					1001 TO 1500 KVA		34500		
Cable Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.				IS 7098 Part 1: 1988 (RA-2015)		1.1KV LT Cable	Each	850
							IS 7098 Part 2: 2011 (RA-2016)	11KV HT Cable	Each
Relay Test	Testing of Relay operating characteristics for any abnormal condition.				IS 9124: 1979 (RA-2011)		--	Per Relay	1700
LT Panel Test	1. Physical examination of Bus-bar as per load, color, Gap b/w each other. 2. Testing of Tripping characteristics of Switchgears.				--		Upto 160A Incomer	Each	2650
							With MCCB Incomer	Each	4000
							With Motorised MCCB Incomer	Each	6600
		With ACB Incomer	Each	11500					

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site											
3	Hotel Testing Kit	Earth Testing	Measurement of Earth Resistance.	IS 3043: 1987 (RA 2016)	--	Per Pit	700				
		Energy Meter Testing	Check meter reading is accurate or not.	IS 15707: 2006 (RA 2016)	Single Phase	Each	600				
		LUX Measurement	Check light level for a particular area.	IS 3646 PART-1 1992 (RA 2008)	Three Phase	Each	850				
					Guest Rooms	Per Room	200				
					Other Areas						
					Upto 100 Sqmtr.	Per Job	5200				
					101 - 300 Sqmtr.	Per Job	8600				
		301 - 500 Sqmtr.	Per Job	17250							
		Above 500 Sqmtr.	Per Sqmtr.	50							
		Wire Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 694 : 2010 (RA 2015)	--	Per Circuit	100				
		Polarity Test for Switch	Check that apparatus have correct connectivity.	IS 732: 1989 (RA 2015) Clause 12.3.10	--	Per Switch Board	50				
		Visual Inspection of MCB, ELCB & Distribution Board as per load	Check ratings and connectivity is ok or not.	IS/IEC 60898-1: 2002 Clause 9.10.1	Single Phase	Per Dist. Board	500				
					Three Phase	Per Dist. Board	850				
		Transformer Test	1. Oil Level Checking in Conservator 2. No Load Loss & Current 3. Terminations Connections on HV & LV Cable Box 4. Short Circuit Impedance & Load Loss at 50% & 100% Load 5. Oil & Winding Temperature Measurement & Inspection of Buchholz Relay 6. Insulation Resistance & Winding Resistance Test 7. Voltage Ratio Test 8. Magnetic Balance Test 9. Phase Displacement Test 10. Oil Break Down Voltage Test (In Lab)	IS 10028 Part 3: 1981 (RA-2008)	Upto 250 KVA	Each	20000				
					251 TO 500 KVA		24000				
					501 TO 1000 KVA		28750				
					1001 TO 1500 KVA		34500				
					Cable Insulation Resistance Test		Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 7098 Part 1: 1988 (RA-2015)	LT Cable	Each	850
									IS 7098 Part 2: 2011 (RA-2016)	11KV HT Cable	Each
					Relay Test		Testing of Relay operating characteristics for any abnormal condition.	IS 9124: 1979 (RA-2011)	--	Per Relay	1700
LT Panel Test	1. Physical examination of Bus-bar as per load, color, Gap b/w each other. 2. Testing of Tripping characteristics of Switchgears.				-		Upto 160A Incomer	Each	2650		
							With MCCB Incomer	Each	4000		
							With Motorised MCCB Incomer	Each	6600		
		With ACB Incomer	Each	11500							

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site											
4	Institutional Building Testing Kit	Earth Testing	Measurement of Earth Resistance.	IS 3043: 1987 (RA 2016)	--	Per Pit	700				
		Energy Meter Testing	Check meter reading is accurate or not.	IS 15707: 2006 (RA 2016)	Single Phase	Each	600				
		LUX Measurement	Check light level for a particular area.	IS 3646 PART-1 1992 (RA 2008)	Three Phase	Each	850				
					Class room	Each	450				
					Other Areas						
					Upto 100 Sqmtr.	Per Job	3450				
					101 - 300 Sqmtr.	Per Job	5750				
		301 - 500 Sqmtr.	Per Job	12000							
		Above 500 Sqmtr.	Per Sqmtr.	50							
		Wire Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 694 : 2010 (RA 2015)	--	Per Circuit	100				
		Polarity Test for Switch	Check that apparatus have correct connectivity.	IS 732: 1989 (RA 2015) Clause 12.3.10	--	Per Switch Board	50				
		Visual Inspection of MCB, ELCB & Distribution Board as per load	Check ratings and connectivity is ok or not.	IS/IEC 60898-1: 2002 Clause 9.10.1	Single Phase	Per Dist. Board	500				
					Three Phase	Per Dist. Board	850				
		Transformer Test	1. Oil Level Checking in Conservator 2. No Load Loss & Current 3. Terminations Connections on HV & LV Cable Box 4. Short Circuit Impedance & Load Loss at 50% & 100% Load 5. Oil & Winding Temperature Measurement & Inspection of Buchholz Relay 6. Insulation Resistance & Winding Resistance Test 7. Voltage Ratio Test 8. Magnetic Balance Test 9. Phase Displacement Test 10. Oil Break Down Voltage Test (In Lab)	IS 10028 Part 3: 1981 (RA-2008)	Upto 250 KVA	Each	20000				
					251 to 500 KVA		24000				
					501 to 1000 KVA		28750				
					1001 to 1500 KVA		34500				
					Cable Insulation Resistance Test		Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 7098 Part 1: 1988 (RA-2015)	LT Cable	Each	850
					IS 7098 Part 2: 2011 (RA-2016)			11KV HT Cable	Each	3450	
					Relay Test		Testing of Relay operating characteristics for any abnormal condition.	IS 9124: 1979 (RA-2011)	--	Per Relay	1700
LT Panel Test	1. Physical examination of Bus-bar as per load, color, Gap b/w each other. 2. Testing of Tripping characteristics of Switchgears.				-		Upto 160A Incomer	Each	3450		
							With MCCB Incomer	Each	5200		
							With Motorised MCCB Incomer	Each	8600		
		With ACB Incomer	Each	11500							

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site								
5	Hospital/ Industrial Testing Kit	Earth Testing	Measurement of Earth Resistance.	IS 3043: 1987 (RA 2016)	--	Per Pit	850	
		Energy Meter Testing	Check meter reading is accurate or not.	IS 15707: 2006 (RA 2016)	Single Phase	Each	600	
					Three Phase	Each	850	
		LUX Measurement	Check light level for a particular area.	IS 3646 PART-1 1992 (RA 2008)	Upto 100 Sqmtr.	Per Job	5200	
					101 - 300 Sqmtr.	Per Job	8600	
					301 - 500 Sqmtr.	Per Job	17250	
					Above 500 Sqmtr.	Per Sqmtr.	50	
		Wire Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 694 : 2010 (RA 2015)	--	Per Circuit	100	
		Polarity Test for Switch	Check that apparatus have correct connectivity.	IS 732: 1989 (RA 2015) Clause 12.3.10	--	Per Switch Board	50	
		Visual Inspection of MCB, ELCB & Distribution Board as per load	Check ratings and connectivity is ok or not.	IS/IEC 60898-1: 2002 Clause 9.10.1	Single Phase	Per Dist. Board	500	
					Three Phase	Per Dist. Board	850	
		Transformer Test	1. Oil Level Checking in Conservator 2. No Load Loss & Current 3. Terminations Connections on HV & LV Cable Box 4. Short Circuit Impedance & Load Loss at 50% & 100% Load 5. Oil & Winding Temperature Measurement & Inspection of Buchholz Relay 6. Insulation Resistance & Winding Resistance Test 7. Voltage Ratio Test 8. Magnetic Balance Test 9. Phase Displacement Test 10. Oil Break Down Voltage Test (In Lab)	IS 10028 Part 3: 1981 (RA-2008)	upto 250 KVA	Each	20000	
					251 to 500 KVA		23800	
					501 to 1000 KVA		28750	
					1001 to 1500 KVA		34500	
					Cable Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 7098 Part 1: 1988 (RA-2015)	LT Cable
IS 7098 Part 2: 2011 (RA-2016)	11KV HT Cable						Each	3450
Relay Test	Testing of Relay operating characteristics for any abnormal condition.				IS 9124: 1979 (RA-2011)	--	Per Relay	1700
LT Panel Test	1. Physical examination of Bus-bar as per load, color, Gap b/w each other. 2. Testing of Tripping characteristics of Switchgears.				-	Upto 160A Incomer	Each	3450
						With MCCB Incomer	Each	5200
						With Motorised MCCB Incomer	Each	8600
		With ACB Incomer	Each	11500				

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site											
6	Outdoor/ Landscape/ Garden/ Parking/ Open or Terrace Restaurent etc.	Earth Testing	Measurement of Earth Resistance.	IS 3043: 1987 (RA 2016)	--	Per Pit	850				
		Energy Meter Testing	Check meter reading is accurate or not.	IS 15707: 2006 (RA 2016)	Single Phase	Each	850				
					Three Phase	Each	1300				
		LUX Measurement	Check light level for a particular area.	IS 3646 PART-1 1992 (RA 2008)	--	Per Sqmtr.	100				
		Wire Insulation Resistance Test	Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 694 : 2010 (RA 2015)	--	Per Circuit	150				
		Polarity Test for Switch	Check that apparatus have correct connectivity.	IS 732: 1989 (RA 2015) Clause 12.3.10	--	Per Switch Board	100				
		Visual Inspection of MCB, ELCB & Distribution Board as per load	Check ratings and connectivity is ok or not.	IS/IEC 60898-1: 2002 Clause 9.10.1	Single Phase	Per Dist. Board	850				
					Three Phase	Per Dist. Board	1400				
		Transformer Test	1. Oil Level Checking in Conservator 2. No Load Loss & Current 3. Terminations Connections on HV & LV Cable Box 4. Short Circuit Impedance & Load Loss at 50% & 100% Load 5. Oil & Winding Temperature Measurement & Inspection of Buchholz Relay 6. Insulation Resistance & Winding ResistanceTest 7. Voltage Ratio Test 8. Magnetic Balance Test 9. Phase Displacement Test 10. Oil Break Down Voltage Test (In Lab)	IS 10028 Part 3: 1981 (RA-2008)	upto 250 KVA	Each	20000				
							251 to 500 KVA	23800			
					501 to 1000 KVA		28750				
					1001 to 1500 KVA		34500				
					Cable Insulation Resistance Test		Check insulation of a wire which protect conducting material from water, heat & electrical leakage.	IS 7098 Part 1: 1988 (RA-2015)	LT Cable	Each	850
								IS 7098 Part 2: 2011 (RA-2016)	11KV HT Cable	Each	3450
					Relay Test		Testing of Relay operating characteristics for any abnormal condition.	IS 9124: 1979 (RA-2011)	--	Per Relay	1700
					LT Panel Test		1. Physical examination of Bus-bar as per load, color, Gap b/w each other. 2. Testing of Tripping characteristics of Switchgears.	-	Upto 160A Incomer	Each	3450
With MCCB Incomer	Each								5200		
With Motorised MCCB Incomer	Each								8600		
With ACB Incomer	Each	11500									

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site							
A.	Circuit breakers	MCB, MCCB	Tripping characteristics	IS/IEC 60898-1: 2002 Clause 9.10.1	For MCB upto 100 Amp	Each	2300
					For MCCB upto 125 Amp	Each	4000
					For MCCB upto 250 Amp	Each	5750
B.	Electrical Energy Audit	Verification, monitoring and analysis of use of energy.	--	--	Senction Load upto 50 KW	Job	43000
					50- 100 KW	Job	86250
					100- 250 KW	Job	130000
					250- 500 KW	Job	172500
					Above 500 KW	Per KW	350
C.	Post Execution Audit	Inspection, survey & analysis of electrical work, done as per work order	--	--	--	Min Charges	28750
						1% of Work Order	
D.	Cable Fault Locator Service	To determine the exact position of the cable fault	--	--	LT Cable	Per Fault	6900
					11KV HT Cable	Per Fault	11500
					33KV HT Cable	Per Fault	17250
					(Outside Jaipur ₹ 12.00 Per Km. Extra)		
E	DISCOM'S POWER QUALITY TEST	Verification of Parameters of Power Quality	Frequency, Voltage, Reactive Power & Current Harmonics	As per CERC		Per Testing	28750

GST shall be charged Extra as per applicable



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site

Electrical Testing Services At Lab

1	Circuit breakers	MCB, MCCB	Tripping characteristics	IS/IEC 60898-1: 2002 Clause. 9.10.1	For MCB upto 100 Amp	Each	1300
2	Circuit breakers	MCB, MCCB	Tripping characteristics	IS/IEC 60898-1: 2002 Clause. 9.10.1	For MCCB upto 125 Amp	Each	1700
3	Circuit breakers	MCB, MCCB	Tripping characteristics	IS/IEC 60898-1: 2002 Clause. 9.10.1	For MCCB upto 250 Amp	Each	2300
4	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	33 KV XLPE Cable 3 core upto 300 Sqmm	Each	58800
5	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	11 KV XLPE Cable 3 core 185 & 300 Sqmm	Each	49000
6	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	LT XLPE Cable 3.5 /4.0 core 185 & 300 Sqmm	Each	39200
7	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	11 KV XLPE Cable 3 core 150 Sqmm	Each	45750
8	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	LT XLPE Cable 3.5/ 4.0 core upto 10 Sqmm	Each	13100
9	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	LT XLPE Cable 3.5/ 4.0 core 16 & 25 Sqmm	Each	22900
10	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	LT XLPE Cable 3.5/ 4.0 core150 Sqmm	Each	32700
11	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tets	IS 7098 Part-1,2	LT XLPE Cable 2 Core 4 Sqmm, 6Sqmm, 10Sqmm	Each	12650
12	Cable & Wire	LT & HT Cables, PVC Insulated Wires	Various Tests	IS 694 : 2015	PVC insulated Copper/ Aluminium Wire	Each	8300
13	Allumium & All Aluminium Conductors ACSR, AAAC	Ovehead Line Conductors	Various Tests	IS 398 (Part-2) RA2012	Weasel Conductor	Each	15000
14	Allumium & All Aluminium Conductors ACSR, AAAC	Ovehead Line Conductors	Various Tests	IS 398 (Part-2) RA2012	Rabbit Conductor	Each	15000
15	Allumium & All Aluminium Conductors ACSR, AAAC	Ovehead Line Conductors	Various Tests	IS 398 (Part-2) RA2012	DOG Conductor	Each	15000



MEC TEST HOUSE

CURRENT INFRAPROJECTS PRIVATE LIMITED (MEC TEST HOUSE)

A-27, BASANT VIHAR, BAJARI MANDI ROAD, VAISHALI MARG WEST, PANCHYAWALA, JAIPUR-302034, RAJASTHAN INDIA

Price List of Electrical Tests & Services

Rates are effective from 1st APRIL-2021

Electrical Testing Services At Site							
16	Alluminium & All Aluminium Conductors ACSR, AAAC	Ovehead Line Conductors	Various Tests	IS 398 (Part-2) RA2012	Panther Conductor	Each	32400
17	Geyser (Storage Water Heater)	Electric Water Heater	Various Tests	IS 2082 : 2018	Electrical Water Heater	Each	1700
18	Relay	Protection Relay	Pick-Up Value Drop-Out Value and Time Delay	IS 9124: 1979 (RA 2011)	Electromechanical, Induction disc overcurrent relay, Static, Digital, Numerical	Each	2300
19	PVC Conduit Test	PVC Conduit Test	Thickness Test, Overall Diameter Test	IS: 9537 (Part 3) – 1983 RA 2007	PVC Conduit	Each	700
20	Transformer Oil	'Transformer Oil, HT Oil Switch	Electric Strength (BDV) Test	IS 6792:1992 (RA 2008)	Transformer Oil, HT Oil Switch	Each	1700
21	LIGHT FIXTURE TESTING	LED Self Ballast SSL Product	Various Tests	LM-79 (16106 : 2012)	LED Self Ballast SSL Product	Each	40250
22	11kv/0.4kv Distribution Transformer	Distribution Transformer	Various Tets	IS 1180 : 2014 2026 : 2011	Transformer 11KV/0.433KV upto 250KVA	Each	25900
23	11kv/0.4kv Distribution Transformer	Distribution Transformer	Various Tets	IS 1180 : 2014 2026 : 2011	Transformer 11KV/0.433KV above 250KVA	Each	40500

GST shall be charged Extra as per applicable